


System No. F-C-1143

June 13, 2006

F Rating – 1 Hr

T Rating – 1 Hr



1. Floor-Ceiling Assembly – The 1 hr fire-rated wood joist floor-ceiling assembly shall be constructed of the materials and in the manner specified in the individual L500 Designs in the UL Fire Resistance Directory, as summarized below:

A. Flooring System – Lumber or plywood subfloor with finish floor of lumber, plywood or Floor Topping Mixture* as specified in the individual Floor-Ceiling Design. Max diam of opening is 5 in.

B. Wood Joists – Nom 10 in. deep (or deeper) lumber, steel or combination lumber and steel joists, trusses or Structural Wood Members* with bridging as required and with ends firestopped.

C. Gypsum Board * – Nom 5/8 in. thick as specified in the individual Floor-Ceiling Design.

2. Chase Wall – The through penetrants (Item 3) shall be routed through a 1 hr fire-rated single, double or staggered wood stud/gypsum board chase wall constructed of the materials and in the manner specified in the individual U300 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:

A. Studs – Nom 2 by 6 in. lumber or double nom 2 by 4 in. lumber studs.

B. Top Plate – The double top plate shall consist of two nom 2 by 6 in. lumber plates or two sets of parallel 2 by 4 in. lumber plates, tightly butted. Max diam of opening is 5 in.

C. Gypsum Board* – Thickness, type, number of layers and fasteners shall be as specified in the individual Wall and Partition Design.

3. Through Penetrant – One metallic pipe, tubing or conduit installed concentrically or eccentrically within the firestop system. A nom annular space of min 0 in. (point contact) to a max 7/8 in. is required between the penetrant and the periphery of the opening. Pipe, tubing or conduit to be rigidly supported on each side of the floor assembly. The following types and sizes of metallic pipes, tubing or conduit may be used:

A. Copper Pipe – Nom 4 in. diam (or smaller) Regular (or heavier) copper pipe.

B. Copper Tubing – Nom 4 in. diam (or smaller) Type L (or heavier) copper tubing.

C. Steel Pipe – Nom 4 in. diam (or smaller) Schedule 10 (or heavier) steel pipe.

D. Iron Pipe – Nom 4 in. (or smaller) cast or ductile iron pipe.

E. Conduit – Nom. 4 in. diam (or smaller) steel electrical metallic tubing or steel conduit.

4. Firestop System – The firestop system shall consist of the following:

A. Packing Material – Foam backer rod firmly packed into opening as a permanent form. Packing material to be recessed from top surface of subfloor and bottom surface of the lower top plate as required to accommodate the required thickness of fill material.

B. Fill, Void or Cavity Material* – Caulk – Min 1/4 in. thickness of fill material applied within annulus, flush with top surface of subfloor and min 1/2 in. thickness of fill material applied within the annulus, flush with bottom surface of lower top plate. At point contact location, 1/4 in. diam bead of caulk applied at interface of penetrant and periphery of opening on top surface of floor and bottom surface of lower top plate

FLAME TECH INC – Firestop-814+

***Bearing the UL Classification Mark**